RAASHI ENTERPRISES
RAJESH JAIN
CIVIL ENGINEERS • CONSTRUCTORS
STRUCTURAL REPAIRS • REDEVELOPEMENT
27, Gyaneshwari CHSL, Peru Baug, Aarey Road,
B/h Pritam Hotel, Goregaon (E), Mumbai - 400 063.
Tel.: 022-2790 4779 • Mob. : 98214 14258 / 98211 73991

21st September, 2022

Hon.Chairman / Secretary,
SAMARPAN CHSL,
Borivali(East), MUMBAI.

Subject : Estimate for Structural Strenghthening, Civil Repairs, Terrace Waterproofing Coating and Painting Works for your building Premises.

ESTIMATE

Sr. No.	Description Of Items	Tentative Quantity	Unit	Rate per Unit	Tentative Est. Amount
1	**Scaffolding** : Providing and erecting sturdy safe scaffolding with nylon net covering and removing the some after work completion.				
1.a	Double Bamboo (for dead walls)	Rate Only	Sft	7.00	Rate Only
1.b	Single Bamboo (for other areas)	36000.00	Sft	4.95	178200.00
2	Removing and refixing the same old m s grill (to be secured by the client/ user); Excluding any repairs/ alteration / modification cost.	Rate Only	Sft	45.00	0.00
3	Covering of M S Grills with Green Net, before doing civil works, wherever required	*3000.00*	Sft	3.60	10800.00
4	Covering window/ door/ balcony openings using Plywood/ covering material and removing the same after completion.	Rate Only	Sft	27.00	0.00
5	Covering outdoor AC units using Plywood/ covering material and removing the same after completion, before doing civil works, wherever required.	4.00	No	900.00	3600.00
6	Providing and fixing safety net, wherever required, complete.	400.00	Sft	18.00	7200.00
7	Providing & fixing necessary platform at the levels to hold the debries at intermediats level as per the requirement with bamboos and plywood	180.00	Sft	18.00	3240.00
8	**Sandfaced Plaster :** Removing existing debonded plaster from external surface and (after necessary repairs) redoing sand face plaster with waterproof additives in two coats at external façade including necessary curing, cleaning, shifting of debris to allocated location.	4000.00	Rft/Sft	94.50	378000.00
9	**Dash coat plaster**	400.00	Rft/Sft	45.00	18000.00
10	**FILLING AND REINSTATING OF SEPARATION CRACKS :**				
	Opening the separation cracks at the junction of RCC and masonary wherever required in to '' V'' Groove of the cracks by carefully marking the areas followed by moistening the cracks, providing and applying priming/bonding coat of cement slurry and applying cement mortar with pvc mesh.	300.00	Rft	*72.00*	21600.00
11	**Internal cement Plaster** : Breaking and removing existing loose internal plaster, wherever required followed by (After necessary repairs treatment) providing and applying single coat cement plaster with bond coat with surrounding junction including necessary curing, cleaning, shifting debris to allocated location.	400.00	Rft/ Sft	67.50	27000.00
12	Internal POP Punning: P/A POP punning on newly plastered surface.	Rate Only	Rft/ Sft	45.00	0.00
13.a	Providing and Covering the flooring with plastic sheet for the protection of the	Rate Only	Sft	4.50	0.00
13.b	Providing and Covering the wall with plastic sheet for the protection of the unit	Rate Only	Sft	4.50	0.00

ESTIMATE

Sr. No.	Description Of Items	Tentative Quantity	Unit	Rate per Unit	Tentative Est. Amount
14	**Structural Repairs:**				
a	Removing loose debonded concerete surface / cover and providing and applying rust remover, followed by rust preventor on exposed reinforcement of steel surfaces.	1000.00	Rft/ Sft	36.00	36000.00
b	P/A EPCO- KP- 100 COROSSION INHIBITOR	10.00	Ltr	*495.00*	4950.00
c	Providing and erecting M.S. props and removing the same after work completion.	10.00	Nos	270.00	2700.00
d	Providing, cutting and fixing reinforcement of steel bars	60.00	kg	117.00	7020.00
e	Grouting: Drilling holes of required size and Providing and fixing 12mm diametre aluminium PVC injection nipples and grouting. Providing and Injecting ,cement grout using non-shrink additives.	30.00	Nos	*180.00*	5400.00
g	Providing and fixing with epoxy, 10mm dia r/f steel pins 4'' to 6'' length in RCC members before jacketing,Micro concreting	30.00	Nos.	117.00	3510.00
h	Providing and applying Hack-aid plast (effective polymer Bonding coat) between old and new concrete/ plaster.	900.00	Sft	*18.00*	16200.00
15	Applying **PMM Treatment:**				
a	Ready to use Hand Repair Mortar :- Providing and Applying Ready to use Mortar (Single Component Polymer Modified Repair Mortar) in layers to exposed RCC Structural members, as per manufactures specifications and as per technical Specification / as instructed by the	6000.00	kg	45.00	270000.00
b	**Polymer Modified Bond Coat :** P/L of required polymer modified bond coat etc., including all necessary equipments. (Weight of Polymer used to be counted).	100.00	Litres	396.00	39600.00
16	Applying **Super Fluid Micro Concrete**:				
a	Providing and erecting shuttering for microconcreting, concreting etc. and removing the same after completion, complete.	100.00	Rft/ Sft	144.00	14400.00
b	Providing and Pouring Super Fluid Micro Concrete as per Manufacturers Specification, curing etc.,complete.	900.00	kg	54.00	48600.00
17	**Terrace / Chajja / Balcony waterproofing :**				
a	**Total waterproofing** (10 Years Warranty) including breaking existing wp treatment (avg. 112 mm thick), cleaning slab, providing and applying basecoat, brick bat waterproof coba, china mosaic, complete, in best workmanship manner.	Rate Only	Rft/ Sft	306.00	0.00
	OR				**OR**
b	**Top Layer Waterproofing** (5 years Warranty) Removing loose top layer (upto BB coba IPS top), providing and applying chemical base coat, providing and applying china mosaic etc., complete	Rate Only	Rft/ Sft	144.00	Rate Only
	OR				**OR**
c	Providing and applying **waterproof chemical coating** sandwitched with fibre mesh on existing **intact** terrace top as well as parapet wall top and inside,(The terrace and parapet wall must have good intact surface and must be with required adequate slope, outlets, etc.)	7900.00	Rft/ Sft	63.00	497700.00
d	Grouting (For Waterproofing): Drilling holes of required size and Providing and fixing 12mm diametre aluminium PVC injection nipples and grouting. Providing and Injecting ,cement grout using non-shrink additives.	40.00	Nos	*369.00*	14760.00
18	Providing and making joint sealing/ vata above weather shed	3000.00	Rft	*117.00*	351000.00
19	**Carting aways debris (W/o any MCGM debris permission)**	47.00	Cu M	855.00	40185.00
20	**EXTERNAL PAINTING** (on existing scaffolding)				
a	Applying one coat of Basecoat and 2 coats of premium quality elastomaric paint of asian/ Nerolac/ICI or equivalent (Note : same scaffolding erected for civil works to be used Ext painting works.) **(10 years paint company warranty)**	40000.00	Sft	*19.80*	792000.00

ESTIMATE

Sr. No.	Description Of Items	Tentative Quantity	Unit	Rate per Unit	Tentative Est. Amount
b	Providing all material and labour for painting , plain steel surface grill etc,including , scrapping existing paint applying one coat primer, filling, with painters putty and finishing with 2 coats of approved quality of synthetic enamel paint on M.S. grill	16000.00	Sft	14.40	230400.00
21	**INTERNAL PAINTING**				
	Scrapping existing loose paint cleaning all surface carrying out surface priming and application of semi acrylic paint in staircase area and common passage area.	19000.00	Sft	*11.70*	222300.00
TAXES EXTRA				**TOTAL AMOUNT**	**32,44,365.00**
TAXES EXTRA	Contigencies @ 15% (For Unforeseen items and quantities)				4,86,654.75
TAXES EXTRA				TOTAL AMOUNT	37,31,019.75

ESTIMATE (PIT PARKING RELATED WORK)

Sr. No.	Description Of Items	Tentative	Unit	Rate per	Tentative Est.
1	Backfilling existing parking pit using good quality material in layers of 6" with necessary compaction upto base level for soling, complete. (Material to be supplied by the society at exact work location, Free of cost).	6000.00	Cft	18.00	108000.00
2	Providing and doing 8" thick Rubble Soling including necessary compaction, on compacted backfilled material.	1100.00	Sft/ Cft	54.00	59400.00
3	P/C/Binding reinforcement steel for the slab.	700.00	Kg	*99.00*	69300.00
4	Providing and Laying 6" thick M20 grade concrete for the slab (Without any shuttering work)	1100.00	Rft/ Sft	162.00	178200.00
TAXES EXTRA				**TOTAL AMOUNT (Pit Parking Related Works)**	**4,14,900.00**

ESTIMATE (PLUMBING AND DRAINAGE WORK)

Sr. No.	*Description Of Items*	*Tentative Quantity*	*Unit*	*Rate per Unit*	*Tentative Est. Amount*
	This Plumbing and Drainage related works will be carried out subject to access to work location; Any additional cost for the same will be put to you, if necessary.				
1	**Plumbing/ Drainage**: Removing existing complete pipeline and fixing new PVC drainage line.(W/o any temporary line cost).				
a	4" dia Soil Waste	*Rate Only*	Rft	144.00	Rate Only
b	3" dia waste-water	*Rate Only*	Rft	126.00	Rate Only
c	4" dia Rainwater	*Rate Only*	Rft	135.00	Rate Only
d	2.5" dia Vent	*Rate Only*	Rft	99.00	Rate Only
2	**Plumbing/ Drainage**: Removing existing all pipeline fixtures/ specials and fixing new PVC drainage specials/ connectors, etc.				
a	4" dia	*Rate Only*	No.	396.00	Rate Only
b	3" dia.	*Rate Only*	No.	360.00	Rate Only
c	2.5" dia	*Rate Only*	No.	306.00	Rate Only
3	**PLUMBING GABDAs**: Breaking and making gabda for drainage points and refilling the same after completion of plumbing work.	*Rate Only*	No	450.00	Rate Only
4	**G.I. Brackets and U bolts:** (Per U bolt to be counted)	*Rate Only*	No	99.00	Rate Only
5	**Temporary Drainage line (Full pipe height and length to be considered) Old Existing available pipes to be used**				
a	4" dia Soil Waste	*Rate Only*	Rft	81.00	Rate Only
b	3" dia waste-water	*Rate Only*	Rft	72.00	Rate Only
6	C I **Drainage at Ground Level (WITHOUT New C I pipes/ Fittings)** :				
a	4" dia Soil Waste	*Rate Only*	Rft	117.00	Rate Only

ESTIMATE

Sr. No.	Description Of Items	Tentative Quantity	Unit	Rate per Unit	Tentative Est. Amount
b	3" dia waste-water	*Rate Only*	Rft	117.00	Rate Only
c	4" dia Rainwater	*Rate Only*	Rft	99.00	Rate Only
d	2.5" dia Vent	*Rate Only*	Rft	108.00	Rate Only
6	***Plumbing Works : UPVC Water pipelines : (Indicative Quantities only)***				
	Providing and fixing UPVC water line pipes with fittings including,removing existing pipes,fittings, etc., complete.				
	a) 1/2 '' dia Pipes with fittings	Rate Only	*Rft*	*117.00*	*Rate Only*
	b) 3/4'' dia.pipes with fittings.	Rate Only	*Rft*	*153.00*	*Rate Only*
	c) 1'' dia pipes with fittings	Rate Only	*Rft*	*189.00*	*Rate Only*
	d) 1 1/4'' dia pipes with fittings	Rate Only	*Rft*	*234.00*	*Rate Only*
	e) 1 1/2'' dia pipes with fittings	Rate Only	*Rft*	*297.00*	*Rate Only*
	f) 2'' dia pipes with fittings	Rate Only	*Rft*	*414.00*	*Rate Only*
	g) 2 1/2'' dia pipes with fittings	Rate Only	*Rft*	*630.00*	*Rate Only*
7	***G.I. Brackets and U bolts: (Per U bolt to be counted)***	Rate Only	*Nos*	*99.00*	*Rate Only*
8	*Removing exisiting and providing New UPVC Ball Valve*				
	i) 2 1/2'' Dia	Rate Only	*Nos*	*3600.00*	*Rate Only*
	i) 2'' Dia	Rate Only	*Nos*	*1440.00*	*Rate Only*
	i) 1 1/2'' Dia	Rate Only	*Nos*	*1170.00*	*Rate Only*
	ii) 1 1/4'' Dia	Rate Only	*Nos*	*900.00*	*Rate Only*
	iv) 1'' Dia	Rate Only	*Nos*	*765.00*	*Rate Only*
	v) 3/4'' Dia	Rate Only	*Nos*	*675.00*	*Rate Only*
	vi) 1/2'' Dia	Rate Only	*Nos*	*495.00*	*Rate Only*
9	*Providing & fixing UPVC barrel pieces of any dia. (W/o any internal civil, Finishing works)*	Rate Only	*Nos*	*990.00*	*Rate Only*
TAXES EXTRA	***TOTAL ESTIMATED AMOUNT (PLUMBING AND DRAINAGE WORK)***				**-**

CONSIDERATIONS

1. All quantities mentioned above are tentative, and may VARY as per work requirement; However billing will be as per actual work delivered.
2. Any extra item arises, it will cost you extra.
3. Water,Electricity, Place (including labour hutments) for work, Material stacking and labour to be given by you, Free of Cost.
4. IF Your Building Premises does NOT have Open Space for UNLOADING of Materials; which may cause inconvenience to members/ visitors AND it also may attract penalties by LOCAL AUTHORITIES; THESE ALL COST, PROVISIONS HAVE TO BE BORNE BY THE CLIENT (SOCIETY).
5. Rates mentioned above are **excluding** all taxes.
6. Permission, Charges etc for BMC, any other govt.,semi-govt. organization, if required, then to be obtained by you.
7. Cost for any STRUCTURAL STABILITY CERTIFICATE is not included in the above Estimate.

We hope and trust that you will find the above offer in order and would request you to contact us in case you require any further details / clarifications.

Yours' Faithfully,

For RAASHI ENTERPRISES

PARTNER